



Staging &
Structures

IPS 16/20/24m PR15 Roof



16m PR15 with custom Layher Facade,
Greenman Festival, Brecon Beacons



PR15 with side wings, and cowsheds,
Music Plus Sport, Northampton



PR15 with side wings, and cowsheds,
Meadowlands Festival, Nottingham

- ▶ Large format Outdoor Roof Stage in 16, 20 or 24m widths
- ▶ Integral Layher stage substructure
- ▶ All Black Structure Finish, including Truss & Keder profiles
- ▶ Up to 24m wide by 15m deep performance area
- ▶ Up to 65,000Kg roof loading
- ▶ Ideal for audiences of up to 75,000 people

For more information or to check availability and pricing,
contact **IPS** on 01908 657950



IPS 16/20/24m PR15 Roof



PR15 structure during construction

Structure Options:

- ▶ 16m , 20m & 24m Structure Width options
- ▶ 11m or 14m Structure Trim Height options
- ▶ 4m wide full depth integrated side cowsheds
- ▶ 4m deep full width integrated rear changeover shed
- ▶ 6m or 10m wide Truss Wings for PA/Branding/LED Screen with PA outhang positions
- ▶ Additional cross stage truss bridges to increase roof loading
- ▶ Various Step & Ramp Access configurations

Ballast Configurations:

- ▶ Ground Anchors
- ▶ Water Ballast (subject to suitable onsite supply)
- ▶ Concrete Blocks

Standard Configuration:

- ▶ IPS 20m PR15 Roof with Layher stage platform substructure at 2m high with two sets of steps and handrails to rear & sides. Five cross stage truss bridges. Ballast via ground anchors.

PR15 Roof Onsite Details (based on standard configuration)	
Build Times:	3 - 4 Days
De-Rig Times:	2 Days
Access Requirements:	Suitable Access to build location for multiple Articulated Trucks and crane (Trackway)
Site & Plant Requirements:	Approval for use of ground anchors Three Phase power supply Telehandler or All Terrain Forklift Cherry Picker