



Staging &
Structures

IPS 16/20/24m PR15 Roof



PR15 with 6m LED Screen wings



PR15 Roof in action



PR15 with side wings, side and rear cowsheds

IPS 16/20/24m PR15 Roof Key Features:

- ▶ Large format Outdoor Roof Stage in 16, 20 or 24m widths
- ▶ Integral Layher stage substructure
- ▶ All Black Structure Finish, including Truss & Keder profiles
- ▶ Up to 24m wide by 15m deep performance area
- ▶ Can be built without a crane
- ▶ Up to 65,000Kg roof loading
- ▶ Ideal for audiences of up to 75,000 people

For more information or to check availability and pricing, contact **IPS** on 01908 657950



IPS 16/20/24m PR15 Roof



PR15 structure during construction

IPS PR15 Roof Options:

- ▶ 16m , 20m & 24m Structure Width options
- ▶ 11m or 14m Structure Trim Height options
- ▶ 4m wide full depth integrated side cowsheds
- ▶ 4m deep full width integrated rear changeover shed
- ▶ 6m or 10m wide Truss Wings for PA/Branding/LED Screen with PA outhang positions
- ▶ Additional cross stage truss bridges to increase roof loading
- ▶ Various Step & Ramp Access configurations

Ballast Configurations:

- ▶ Ground Anchors
- ▶ Surface Ballast Options of Water or Concrete

Standard Configuration:

- ▶ IPS 20m PR15 Roof with Layher stage platform substructure at 2m high with two sets of steps and handrails to rear & sides. Five cross stage truss bridges. Ballast via ground anchors

PR15 Roof Onsite Details (based on standard configuration)	
Build Times:	3 - 4 Days
De-Rig Times:	2 Days
Site Requirements:	Suitable Access to build location (Trakway) Three Phase Power
Access Requirements:	Articulated Truck
Plant Requirements:	Telehandler or All Terrain Forklift Cherry Picker